



**Summit 7 Series
Performance Equipment
STE112177**

Body Construction

- 12 ga galvanized steel, 11' LG
- 22" D side packs
- 50" W cargo floor
- 62" T D1 & P1 compartments
- 50" T D2,D3 & P2-P4 compartments
- Tie-down rings on cargo area walls: Qty 6
- Aluminum bonded doors with full-length piano-style hinges
- Automotive-style weatherstripping
- Ergonomic overmolded three-point compression door latches
- Aluminum drip rail over compartment doors

Summit Drawer Systems

Aluminum Combo Drawer Pack

- Drawer pack PN: TDRSA-52T-30L-03-02-01-22R-00-01-03
 - 52" W x 18" D overall
 - Top 52" W x 18"
 - One 5" full-width top drawer
 - Left side: 30" W x 18" D
 - Three 3" drawers
 - Two 5" drawers
 - One 7" drawer
 - Right Side: 20" D x 18" D
 - One 5" drawer

- Three 7" drawers
 - The top shelf spans the full width of the compartment.

Aluminum Drawer Pack

- Drawer Pack PN: DRSA-36W-02-01-00-18D-WT aluminum drawer pack
- 36" wide X 18" deep
 - Two 3" drawers
 - One 5" drawer
- Integrated top shelf

Torch Storage Compartment

- The front section has a reinforced floor, upper & lower vents
 - Torch bottle retainer w/ratchet strap
- The rear section has unistrut & adjust. aluminum shelves: Qty 2

Electrical & Lighting

- LED S/T/T light package
 - Flush-mounted in bumper & light bar
- LED compartment lights
- LED Work Lights
 - Rigid 115-Degree Scene Lights: Qty 6
 - Standard Rect.: Qty 2
- Seven-way RV-style trailer plug
- Backup alarm
- Pinnacle lightbar
- Backup camera

Additional Features

- Standard headache rack
- 24" tool bumper
 - 2.5" receiver tube
 - Built-in grip strut step on both sides
 - Bumper hitch Step
 - Seven-way RV-style trailer hitch
- Grab handles: Qty 2

- 12" H tailgate
- Hose retainer
- Full-length riser on top of DS sidepack
- Bolt-in bulkhead
- 5 lb fire extinguisher
- Warning triangles: 3 pk

Summit Model 829 Telescopic Crane NEW MODEL

- Fully proportional hydraulic system
- Planetary winch @ 60' per minute
- Auto-release hook stow
- Boom support and hook anchor
- 26 gal hyd reservoir
- Full hyd rear outriggers
- ASE Phase 5 Control System (Put the ASE Phase 5 logo on the spec sheet)

Reliant RC-40 reciprocating air compressor

- 40 CFM @ up to 175 PSI
- Hannay Reels spring rewind reel
 - 1/2" x 50' hose assembly
- 15 gal under-body air storage tank
- 26-gal hydraulic low-profile reservoir

Miller Bobcat™ 265 Gas w/ Battery Charge Crank

- Processes: Stick, MIG Flux-cored, DC TIG
- Battery Charge/Crank Assist
- 50' of 1/0 hot and ground leads
- 300A electrode holder and ground clamps
- Saf-T Booster cable set

Paint & Finish

- PPG Paint Process
 - Paint: Agate Black

- Body exterior & crane
 - Paint: Lime Green
 - Welder & air compressor
- Vortex Protective Coating
 - Cargo area, rear bumper, work surface & steps
 - Fronts, sides, tops, the rear, & lower edge of side packs
 - Wheel well reinforcement
- Rubberized Protective Coating
 - Underside of the body
- Custom Graphics Package
 - Designed & installed by Yellow Frog Graphics

Chassis Specifications

- 2026 Ford F-600 4X4 RC
- GVWR: 22,000
- Engine: 6.7L Power Stroke® V8 Turbo Diesel
 - HP: 330
- Transmission: 10R140 TorqShift®
 - 10-Spd SelectShift® Automatic
- CA: 84"
- WB: 169.3"
- Wheels: 19.5" x 6.75"
- Tires: 245/70Rx19.5G BSW